

WEST BENGAL FOREST AND BIODIVERSITY CONSERVATION SOCIETY
OFFICE OF THE CHIEF PROJECT DIRECTOR
LB-2, SECTOR-III, SALT LAKE, KOLKATA-700098
NOTICE INVITING QUOTATION

NIQ. NO. 9 /WBFBCP-2015-16 vide no. 631 /WBFBCP/ 12-1 / 2015 dated 27.02.2016

Sealed Quotation is invited from experienced, bonafide and reputed Contractors/ Companies/ Firms for doing the following works for making pantry room, Urinal (2 units) with MS structural work with roof shade etc. on the roof top. of the office of WBFBC Project as detailed below:-

Details of work:-

Sl No.	Item of work	Unit	Quantity	Rate	Amount
1	125 mm thick brick work with 1st class brick in cement mortar (1:4) in ground floor (i-29, pg-31 of PWD 2014)	Sq m	5		
2	Plaster of wall, floor and ceiling etc with sand and cement mortar taking out joint of cement surface where necessary. i) with 6:1 cement mortar 20mm thick plaster(i-2, pg-161 of PWD 2014)	Sqm	12		
3	Ordinary cement concrete (mix1:2:4) with graded stonechips (200mm thick nominal size) excluding shuttering and reinforcement. a) Pakur variety (i-5, pg-11 of PWD 2014)	CuM	1		
4	Supplying, fitting and fixing best Indian sheet glass panes set in putty and fitted and fixed with teak wood beads and nails complete(4mm thick) (i-2(ii), pg-166 of PWD 2014)	Each	1		
5	Supplying, fitting, fixing Marble slab/ tile of 15 to 18 mm thickness in floor, lobby, stair, landing & treads etc. over 20 mm (av.) thick base of cement mortar (1:2) laid with cement slurry @ 4.4 kg/sq.m. before placing marble & jointed with white cement slurry @ 2.0 kg/sq.m. with necessary pigments incl. grinding and granite polishing as per direction in gr. floor.b) with chawk dungri white ii) area of each tile exceeding 0.3 sq.m. but not exceeding 0.6 Sq.(i-23b(ii), pg-48-49 of PWD 2014)	Sq m	1.8		

6	Wood work in door / window frame fitted and fixed in position complete including a protective coat of paint at the contract surface of frame excluding cost of concrete, iron butt hinges and and M.S.Clamps (1) Siliguri Sal.....(i-3(i), pg-86 PWD of 2014)	m3	.4		
7	Supplying and fitting , fixing decorative lamination conforming to IS : 2046:1995 as per approved make, brand, finish, thickness of 1.5mm with fitting fixing the same on particle boards with recommended/approved with proper clipping the sides for better attachment as per direction of engineer-in-charge. The includes the cost of labour adhesive and all incidental charges. (i-121, pg-126 of PWD 2014)	Sq m	13.5		
8	Supplying flush solid doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide weach and the entire frame fitted with 37.5..wide battens placed both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position but excluding the cost of hinges and other fittings at all elevations: (a) 35mm. thick shutters (single leaf) (i-101a, pg-119 of PWD 2014)	Sq m	5.5		
9	Anodised aluminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (IS:230/72) fitted and fixed complete. With round base : 100mmx10mm dia Rod (i-65b(ii), pg-100 of PWD 2014)	Each	2		

10	Supplying Hydraulic door closer of approved quality as per I.S.I standard fitted fixed. (Medium) (i-43b, pg-96 of PWD 2014)	Each	3		
11	Iron Parilamentary hinges conforming to IS 362-1982 fitted and fixed complete with steel screws (90mmx100mmx20mmx2.4mm) (i-21d, pg-91 of PWD 2014)	Each	6		
12	Supplying godrej mortice lock chromium plated with latch and keys, 4 levers, including fitting, fixing complete. (i-36a, pg-95 of PWD 2014)	Each	2		
				TOTAL	

The intending bidders are requested to quote rate for each items separately. Necessary guidelines to be provided in the above matters as and when required.

The quotation should be submitted in the office of WBFBC Project either directly or by mail on or before 8th March, 2016.



**Additional Project Director
Implementation
WBFBC Project**

Copy to Notice Board of the Office of

1. The Chief Project Director, West Bengal Forest and Biodiversity Conservation Society
2. The Principal Chief Conservator of Forests (HOFF), West Bengal
3. Web Site of WBFBP. org



**Additional Project Director
Implementation
WBFBC Project**